

## ***SIDEWALKS AND RIGID PAVEMENT***

---

**General:** Exterior walks and paved areas constructed in conjunction with new building projects shall conform to the requirements of these guidelines.

This work shall consist of preparatory work and operations, associated with the necessary movement of personnel, equipment, supplies and incidentals to the project site and for all the work and operations which must be performed or costs that are necessarily incurred prior to commencing the work. The Contractor shall include all expected costs for movement of all equipment and material necessary to execute the work, including any demobilization. Additional payments will not be made for interruptions in the completion of the Project if the Contractor fails to adequately assess the actual costs of mobilization.

This work shall include the removing of existing pavement, surface and base courses, concrete headers, combination curb and gutter, concrete curb, concrete gutter, concrete driveways, walks, steps, ramps, retaining walls, reinforcement and miscellaneous masonry, as required; and shall also include salvaging and disposing of the resulting material, together with the necessary excavation and backfilling.

Snow Removal Considerations: The requirement for snow removal from all paved surfaces shall be recognized in the layout and construction of walks and paving. Areas which can only be cleaned by hand removal should be kept to an absolute minimum. Ramps should be provided between changes of level in paved areas to allow movement of tractor-mounted plows and/or blowers. Walks and steps with snow melt systems shall include provisions to intercept and remove melted water so that it will not refreeze on adjacent paved areas which do not have snow melt systems.

The University's Civil Engineer/Project Manager shall identify all areas of authorized pavement removal. The removal of existing pavement shall extend to an existing joint, or to the limits shown on the plans. When called for on the plans or by the University's Civil Engineer/ Project Manager, all pavement to be removed shall be isolated from the pavement to remain by cutting a saw joint, as provided below, or by other methods specifically approved by the University's Project Manager/ Civil Engineer. The pavement to be removed shall be broken into movable sizes and removed from the site. If the pavement to remain is damaged by the Contractor, the University's Project Manager/ Civil Engineer will order further removal at the Contractor's expense. Pavement which is removed without authorization by the University's Civil Engineer/Project Manager shall be replaced at the Contractor's expense

---

### ***Walks Construction:***

A. Campus Specific Requirements for sidewalk width and thickness:

#### UNL

Sidewalks shall be minimum of 7'-0" wide (narrower walks shall be approved by UNL Landscape Services and FACILITIES, PLANNING & CAPITAL PROGRAMS), 6" thick with welded wire mesh, with ¼" per foot transverse slope.

#### UNO

All sidewalks should be minimum 5 feet wide and 6" thick with no sand base.

## ***SIDEWALKS AND RIGID PAVEMENT***

---

### UNK

Sidewalks with no vehicular traffic shall be 6" thick. Sidewalks with vehicular traffic or mechanical snow removal shall be analyzed for equipment weight and designed accordingly, (generally 6" thickness). A minimum of 4" granular sub-base shall be installed before placing concrete.

B. Sidewalk shall be constructed on subgrade that has been scarified to a depth of 6" and compacted to a uniform density of not less than ninety-five percent (95%) of the maximum density (as determined by AASHTO standard method T-99) throughout its entire width. The moisture content of the subgrade shall be between two percent below (-2%) and four percent above (+4%) the optimum moisture content as determined by AASHTO standard method T-99. Up to a two inch (2") layer of crushed concrete or sand may be placed on the subgrade as a leveling course. The crushed concrete shall be compacted with a plate compacter and moistened by light application of water prior to concrete placement. The width of the compacted subgrade shall extend 6" past the width of the sidewalk on both sides.

C. Welded wire reinforcing is required for all new sidewalk and ramp concrete. 6 X 6 W1.4xW1.4 wire shall be supported by epoxy coated bolsters so that it is held at mid-depth of the new concrete. Bolsters shall be spaced no more than 3 feet apart. Care shall be taken so that the welded wire reinforcing remains at mid-depth during concrete pouring operations

D. Walks designated as fire lanes shall be a minimum of 8" thick. Reinforcing steel for fire lanes shall be at a minimum of a single mat of #5 size deformed grade 40 reinforcing steel spaced at 12" on center each way. Additional reinforcing for fire lanes may be required.

E. The sidewalk shall extend above the adjacent finished grade by 2".

F. The concrete for the rigid paving shall be City of Lincoln/City of Omaha/City of Kearney (2020 Standard Specifications) L-3500 mix producing a minimum compressive strength of 3500 psi at the end of the 28 day curing period. The concrete shall meet the following requirements when tested onsite:

## ***SIDEWALKS AND RIGID PAVEMENT***

---

### UNO

All paving shall receive a light broom finish. Broom lines are to run perpendicular to foot traffic. All exposed concrete edges to have one half inch (1/2") radius. Unless otherwise noted or approved by the University's Project Manager/ Civil Engineer.

### UNK

Sidewalk finishing shall conform to UNK Design Guideline-Concrete Specification. Broom finish is preferred on sidewalks, and the minimum of 9 square feet for score lines shall not preclude smaller patterns when incorporating design decisions.

H. Immediately after the concrete has been finished, the concrete surface shall be sealed with a uniform application, no less than 1 gallon per 200 square feet, of white pigmented membrane cure ASTM designation C309, Type 1, Class A.

I. Campus Specific requirements for Joints:

### UNL

Control joints shall be cut in green concrete (less than 24 hours old) using a diamond blade with a crack chaser. Depth shall be one-fourth (1/4) of slab depth. Joint locations shall be approved by UNL prior to placement. A longitudinal control joint is required if walk width is greater than 8'-0".

### UNO

Dowel all cold joints

### UNK

Areas with potential for differential settling should be identified and details provided for control joints and expansion joints.

J. Full depth expansion joints are to be installed at 50' O/C. Preformed expansion joint material shall be 1/2" and meet ASTM D1751. Joint shall be sealed with polyurethane sealant. Joint shall be cleaned and inspected prior to sealing. Joint locations shall be approved by the University's Project manager/Civil Engineer prior to placement.

K. Whenever concrete pavement construction is stopped for a period of over 30 minutes, a transverse construction joint shall be formed by finishing the concrete to a bulkhead made of at least 2" material cut to the exact cross section of the pavement slab, as shown on the plans.

L. Sidewalk curves shall be formed true and smooth. Project specific jointing patterns may be required by the University's Project Manager/ Civil Engineer.

M. Campus Specific requirements for ADA compliance:

### UNL



## ***SIDEWALKS AND RIGID PAVEMENT***

---

### 2. Fiber reinforced Concrete

- Fiber reinforced concrete is generally not preferred but may be used on a case-by-case basis. The consulting Engineer can decide the type of fibers, diameter of fibers, length of fibers, and dosage as per the concrete mix calculations and also by the recommendation by the manufacturer of the fibers.

### ***Sidewalk Demolition:***

#### Sidewalk Removal

A. The Contractor shall remove the concrete pavement and curbs, if applicable, without damaging the adjacent concrete pavement and curbs. Repair of any damage caused by the operation is at the Contractor's expense.

B. The Contractor shall remove and dispose of all old pavement, reinforcing steel, and all other materials. The repair section shall be removed with minimum disturbance of the underlying foundation course. Any loosened foundation course material shall be removed and replaced with concrete.

C. The Contractor shall cut around the perimeter of the repair area as shown in the plans. All repairs shall be cut so the edges are parallel or perpendicular to the traveled way. Saw overcuts shall be kept to a minimum.

D. The Contractor shall use hand or pneumatic tools to remove the concrete pavement. If the patch is full depth Type C (more than 15 to 45 S.Y.), then a drop hammer may be used to remove

## ***SIDEWALKS AND RIGID PAVEMENT***

---

### ***Exterior stairs and ramps:***

- A. Protection: All stairs and ramps associated with a building shall be covered by the building roof or an overhead canopy when feasible
- B. Stair Proportions: Exterior stairs, including those providing direct access to a building entrance, shall have a tread riser proportion of not more than 7.5:10
- C. Exterior Ramps: Exterior ramps shall conform to ADA requirements. Curb cuts shall not be less than 84" wide to allow mechanical snow removal. Smaller curb cuts must be approved by the University's Project Manager/ Civil Engineer.
- D. Project specific reinforcing details shall be provided in contract documents.
- E. Concrete specifications listed in the previous section (2. Walks) shall be followed for all concrete exterior stairs and ramps as a minimum standard.
- F. All exterior stairs and ramps shall be furnished with stainless steel handrails.

### ***Stoops and landings:***

- A. Provide structurally supported stoops where exit doors swing outward. Anchor stoops to structure in such a manner so as to prevent heaving from frost.
- B. Provide 1/4" per foot slope on stoops and landings outside exit doors for drainage away from the building.
- C. Project specific reinforcing details shall be provided in contract documents.
- D. Concrete specifications listed in the previous section (2. Walks) shall be followed for all concrete exterior stairs and ramps as a minimum standard.